

NOTA DE SERVIÇO DE TERRAPLENAGEM											
ESTACA	BORDO ESQUERDO				EIXO			BORDO DIREITO			
	ALTURA	PROJETO	DIST	i%	TERRENO	PROJETO	CV	i%	DIST	PROJETO	ALTURA
0	-0.096	809.449	4.9500	3.01	809.123	809.300	-0.177	-2.99	4.9500	809.152	-0.288
1	-0.057	808.696	4.9500	3.01	808.375	808.547	-0.172	-2.99	4.9500	808.399	-0.290
2	-0.023	807.943	4.9500	2.99	807.708	807.795	-0.087	-3.01	4.9500	807.646	-0.148
3	0.031	807.191	4.9500	3.01	807.019	807.042	-0.023	-2.99	4.9500	806.894	-0.104
3+12.309	0.065	806.728	4.9500	3.01	806.534	806.579	-0.045	-2.99	4.9500	806.431	-0.155
4	0.089	806.438	4.9500	2.99	806.269	806.290	-0.021	-3.01	4.9500	806.141	-0.124
5	0.112	805.686	4.9500	3.01	805.554	805.537	0.017	-2.99	4.9500	805.389	-0.079
6	0.121	804.924	4.9500	2.99	804.802	804.776	0.026	-3.01	4.9500	804.627	-0.063
7	0.175	804.144	4.9500	2.99	804.082	803.996	0.086	-3.01	4.9500	803.847	-0.012
8	0.067	803.346	4.9500	3.01	803.175	803.197	-0.022	-2.99	4.9500	803.049	-0.057
9	0.221	802.530	4.9500	3.01	802.518	802.381	0.137	-2.99	4.9500	802.233	-0.098
9+8.862	-0.132	802.164	4.9500	3.01	801.861	802.015	-0.154	-2.99	4.9500	801.867	-0.078
10	-0.073	801.704	4.9500	2.99	801.429	801.556	-0.127	-3.01	4.9500	801.407	-0.141
11	-0.143	800.879	4.9500	3.01	800.562	800.730	-0.168	-2.99	4.9500	800.582	-0.184
12	-0.114	800.053	4.9500	2.99	799.781	799.905	-0.124	-3.01	4.9500	799.756	-0.088
13	0.000	799.228	4.9500	3.01	799.004	799.079	-0.075	-2.99	4.9500	798.931	-0.034
13+16.907	0.054	798.530	4.9500	3.01	798.312	798.381	-0.069	-2.99	4.9500	798.233	-0.011
14	-0.033	798.402	4.9500	2.99	798.150	798.254	-0.104	-3.01	4.9500	798.105	-0.052
14+18.021	0.047	797.606	4.9500	2.99	797.501	797.458	0.043	-3.01	4.9500	797.309	0.040
15	0.039	797.512	4.9500	2.99	797.402	797.364	0.038	-3.01	4.9500	797.215	0.037
16	0.027	796.494	4.9500	3.01	796.472	796.345	0.127	-2.99	4.9500	796.197	0.193
17	-0.074	795.347	4.9500	3.01	795.177	795.198	-0.021	-2.99	4.9500	795.050	0.002
18	-0.018	794.071	4.9500	2.99	794.054	793.923	0.131	-3.01	4.9500	793.774	0.242
19	0.233	792.731	4.9500	2.99	792.871	792.583	0.288	-3.01	4.9500	792.434	0.304
20	0.176	791.391	4.9500	2.99	791.694	791.243	0.451	-3.01	4.9500	791.094	0.384
21	0.080	790.051	4.9500	3.01	790.154	789.902	0.252	-2.99	4.9500	789.754	0.385
21+7.009	0.043	789.581	4.9500	2.99	789.688	789.433	0.255	-3.01	4.9500	789.284	0.487
21+19.021	0.115	788.777	4.9500	3.01	788.990	788.628	0.362	-2.99	4.9500	788.480	0.606
22	0.131	788.711	4.9500	3.01	788.936	788.562	0.374	-2.99	4.9500	788.414	0.616
23	0.168	787.335	4.9500	2.99	787.492	787.187	0.305	-3.01	4.9500	787.038	0.665
23+19.021	0.244	785.967	4.9500	3.01	786.198	785.818	0.380	-2.99	4.9500	785.670	0.530
24	0.249	785.894	4.9500	2.99	786.109	785.746	0.363	-3.01	4.9500	785.597	0.514
25	0.443	784.389	4.9500	3.01	784.811	784.240	0.571	-2.99	4.9500	784.092	0.698
25+19.021	0.629	782.897	4.9500	3.01	783.471	782.748	0.723	-2.99	4.9500	782.600	0.818
26	0.641	782.818	4.9500	3.01	783.405	782.669	0.736	-2.99	4.9500	782.521	0.829
27	0.916	781.113	4.9500	2.99	782.035	780.965	1.070	-3.01	4.9500	780.816	1.187
28	1.094	779.217	4.9500	3.01	780.274	779.068	1.206	-2.99	4.9500	778.920	1.317
29	1.239	777.130	4.9500	3.01	778.341	776.981	1.360	-2.99	4.9500	776.833	1.753
29+19.021	1.076	774.967	4.9500	2.99	776.084	774.819	1.265	-3.01	4.9500	774.670	1.678
30	1.073	774.851	4.9500	2.99	775.965	774.703	1.262	-3.01	4.9500	774.554	1.686
31	0.656	772.487	4.9500	3.01	773.259	772.338	0.921	-2.99	4.9500	772.190	1.212
32	0.286	770.122	4.9500	2.99	770.581	769.974	0.607	-3.01	4.9500	769.825	0.929
33	-0.709	767.758	4.9500	3.01	767.349	767.609	-0.260	-2.99	4.9500	767.461	0.139
33+11.597	-0.835	766.386	4.9500	2.99	765.975	766.238	-0.263	-3.01	4.9500	766.089	0.238
34	-0.547	765.393	4.9500	3.01	765.295	765.244	0.051	-2.99	4.9500	765.096	0.469
35	-0.357	763.028	4.9500	2.99	762.768	762.880	-0.112	-3.01	4.9500	762.731	0.133
36	0.067	760.664	4.9500	3.01	760.382	760.515	-0.133	-2.99	4.9500	760.367	0.098

NOTA DE SERVIÇO DE TERRAPLENAGEM											
BORDO ESQUERDO					EIXO			BORDO DIREITO			
ESTACA	ALTURA	PROJETO	DIST	i %	TERRENO	PROJETO	CV	i %	DIST	PROJETO	ALTURA
36+5.505	-0.242	760.013	4.9500	3.01	759.864	759.864	0.000	-2.99	4.9500	759.716	0.167