

NOTA DE SERVIÇO DE TERRAPLENAGEM											
ESTACA	BORDO ESQUERDO				EIXO			BORDO DIREITO			
	ALTURA	PROJETO	DIST	i%	TERRENO	PROJETO	CV	i%	DIST	PROJETO	ALTURA
0	0.106	785.569	3.9000	3.00	785.453	785.452	0.001	-3.00	3.9000	785.335	-0.097
1	0.297	785.905	3.9000	3.00	785.901	785.788	0.113	-3.00	3.9000	785.671	0.041
2	0.321	786.241	3.9000	3.00	786.115	786.124	-0.009	-3.00	3.9000	786.007	0.007
3	0.205	786.577	3.9000	3.00	786.475	786.460	0.015	-3.00	3.9000	786.343	-0.017
4	0.300	786.913	3.9000	3.00	787.014	786.796	0.218	-3.00	3.9000	786.679	0.011
4+16.447	0.140	787.189	3.9000	3.00	787.172	787.072	0.100	-3.00	3.9000	786.955	0.298
5	0.112	787.249	3.9000	3.00	787.133	787.132	0.001	-3.00	3.9000	787.015	0.202
6	0.310	787.585	3.9000	3.00	787.639	787.468	0.171	-3.00	3.9000	787.351	0.040
7	0.116	787.921	3.9000	3.00	787.854	787.804	0.050	-3.00	3.9000	787.687	0.073
8	0.038	788.257	3.9000	3.00	788.239	788.140	0.099	-3.00	3.9000	788.023	0.125
9	0.418	788.593	3.9000	3.00	788.696	788.476	0.220	-3.00	3.9000	788.359	0.207
10	0.276	788.929	3.9000	3.00	789.031	788.812	0.219	-3.00	3.9000	788.695	0.258
11	0.252	789.265	3.9000	3.00	789.331	789.148	0.183	-3.00	3.9000	789.031	0.222
12	0.253	789.601	3.9000	3.00	789.647	789.484	0.163	-3.00	3.9000	789.367	0.175
13	0.210	789.936	3.9000	3.00	789.876	789.819	0.057	-3.00	3.9000	789.702	-0.007
13+2.241	0.196	789.974	3.9000	3.00	789.906	789.857	0.049	-3.00	3.9000	789.740	-0.070