

NOTA DE SERVIÇO DE TERRAPLENAGEM											
ESTACA	BORDO ESQUERDO				EIXO			BORDO DIREITO			
	ALTURA	PROJETO	DIST	i%	TERRENO	PROJETO	CV	i%	DIST	PROJETO	ALTURA
0	0.173	775.587	3.9000	3.00	775.585	775.470	0.115	-3.00	3.9000	775.353	-0.036
1	0.446	775.687	3.9000	3.00	775.611	775.570	0.041	-3.00	3.9000	775.453	-0.049
1+10.000	-0.044	775.737	3.9000	3.00	775.643	775.620	0.023	-3.00	3.9000	775.503	0.061
2	-0.022	775.782	3.9000	3.00	775.591	775.665	-0.074	-3.00	3.9000	775.548	-0.144
3	0.186	775.842	3.9000	3.00	775.656	775.725	-0.069	-3.00	3.9000	775.608	-0.108
4	0.137	775.862	3.9000	3.00	775.610	775.745	-0.135	-3.00	3.9000	775.628	-0.170
5	-0.046	775.842	3.9000	3.00	775.525	775.725	-0.200	-3.00	3.9000	775.608	-0.292
6	0.126	775.782	3.9000	3.00	775.587	775.665	-0.078	-3.00	3.9000	775.548	-0.089
6+10.000	0.111	775.737	3.9000	3.00	775.560	775.620	-0.060	-3.00	3.9000	775.503	-0.045
7	0.100	775.687	3.9000	3.00	775.547	775.570	-0.023	-3.00	3.9000	775.453	0.020
8	0.083	775.572	3.9000	3.00	775.523	775.455	0.068	-3.00	3.9000	775.338	0.054
9	0.415	775.426	3.9000	3.00	775.563	775.309	0.254	-3.00	3.9000	775.192	0.295
10	0.862	775.249	3.9000	3.00	775.492	775.132	0.360	-3.00	3.9000	775.015	0.330
11	0.760	775.041	3.9000	3.00	775.401	774.924	0.477	-3.00	3.9000	774.807	0.183
11+0.456	0.767	775.036	3.9000	3.00	775.404	774.919	0.485	-3.00	3.9000	774.802	0.190